cdpengineers

STORMWATER MANAGEMENT EVALUATION STUDY

for

City of Richmond

Madison County, Kentucky

September, 2013

3250 blazer parkway lexington kentucky 40509 T 859.264.7500 F 859.264.7501 www.cdpengineers.com

Table 5-2
City of Richmond
July, 2013 Capital Project Prioritzation Table

Category	OC-D	OC-I	OC-H	TF-A	OC-A	OC-B	OC-C	OC-G	TC-A	OC-F	OC-E	TC-D	TC-C	TC-B
Planning Ranking	10	10	10	10	10	10	10	8	8	6	6	6	8	6
Structures flooding	10	10	10	10	10	10	8	8	6	6	6	6	4	4
Street Reconstruction	5	5	5	3	4	4	4	3	5	3	3	3	3	5
Cost	3	3	1	2	4	3	2	3	4	2	4	5	5	5
Phases	3	3	5	5	2	3	5	3	2	5	3	1	1	1
Total Points	31	31	31	30	30	30	29	25	25	22	22	21	21	21

Planning Department Rank	Major-10; Significant-8; Some yard/street-6; Yard-4; Minor-2
Structure/Significant Street Flooding	Known-10; Field Investigation-8; unsure from field investigation-6; couldn't confirm-4; not apparent-2
Street Reconstruction	Major street reconstruction-5, no existing curb and gutter and/or sloping yards-4; minor reconstruction-3; none required-1
Cost	$0 to $750K-5; $750K to $1.5M-4; $1.5M to $2.25M-3; $2.25M to $3.0M-2; over $3.0M-1
Phases	1-1; 2-2; 3-3; 4-4; 5 or over-5

Project Key

OC-D	Water Street, Phase 2 at Wellington and Summit	**OC-G**	E. Irvine Street, Irvine View Street
OC-I	Hanover St and Rice Ct Neighborhood	**TC-A**	Wallace and Blair Street
OC-H	Irvine Road / East Main St Watershed	**OC-F**	Four Mile Road
TF-A	Taylor Fork Watershed	**OC-E**	E Irvine Street, North Fairview Street
OC-A	Red House Road	**TC-D**	Lancaster Rd & Breck Street
OC-B	Walnut Street, N. 2nd St., N. 3rd St. Neighborhoods	**TC-C**	Burnam Ct
OC-C	North St, N 3rd, N 2nd, N 1st, N Madison (Downtown)	**TC-B**	Locust & Westover Streets